

# Addendum 2

14 May 2024

<b>Tender</b>	Kalbarri Disaster Recovery Works AGRN965	<b>RFT No.</b>	RFT08/2023
<b>From</b>	Antoinette Krause	<b>Contact</b>	antoinette.krause@ghd.com
<b>Addendum</b>	Addendum 2		

**Tenderers are to acknowledge receipt of this Addendum in their Tender response.**

Query No.	Tender query	Response
1.	Can the tender deadline be extended?	<ul style="list-style-type: none"> <li>– The Shire has confirmed that the tender deadline is being extended to 24 May 2024 at 4pm AWST.</li> <li>– The extension has been granted to allow contractors additional time to make requests for quotes from subcontractors as well as spend additional time on shoring up rock supply.</li> </ul>
2.	Chinaman's Beach geotechnical investigation	<p>A geotechnical investigation was not undertaken, however, a number of test pits were excavated to determine estimated rock levels for the proposed limestone block retaining wall. The depths were measure by HTD surveyors.</p> <p>The data has been attached in Appendix A.</p>
3.	Pricing of materials or products that vary from those specified in the Tender Documentation	<p>Tenderers are required to price the Pricing Schedule as provided (with the amendment as listed in Addendum 1).</p> <p>Should tenderers have alternative products or materials that they would like to recommend, please include these in an Alternative Tender outlining the benefits/reasoning for the proposed change.</p>



**Figure 1** *Chinaman's Beach - Test Pit – central location along work site*



**Figure 2** *Chinaman's Beach – Test Pit – location near the existing shelter (south eastern extent of the work area)*

**Tenderers are to acknowledge receipt of this Addendum in their Tender response.**

# **Appendix A**

**Estimated rock levels**

Client: GHD

JOB Name: Kalbarri Carpark Surveys

Description: Rock level test holes

Surveyed by Hille Thompson & Delfos

Date of Survey: 02/08/2023



HTD Ref: 287-23

Grid Datum: MGA94 z50

Vert Datum: AHD

**Chinamans Beach**

Point No	Easting	Northing	RL (AHD)	Comments
2034	219873.65	6931692.40	0.42	No rock refusal within excavator digging depth (soft limestone layer at bootom of test hole)
2042	219796.72	6931803.16	1.31	ROCK
2038	219807.35	6931791.02	2.66	ROCK (OUTCROP)
2039	219811.48	6931793.09	1.87	ROCK (OUTCROP)
2033	219833.65	6931729.83	0.45	ROCK

***Jakes Pt***

Point No	Easting	Northing	RL (AHD)	Comments
2048	218877.03	6928859.94	3.13	ROCK
2049	218887.53	6928867.58	2.92	ROCK (OUTCROP)
2047	218903.53	6928862.87	3.22	ROCK
2050	218919.60	6928875.66	2.79	ROCK
2046	218934.38	6928867.73	3.37	ROCK
2051	218946.18	6928883.08	2.78	ROCK
2044	218966.07	6928878.33	3.26	ROCK